




PRODUCT OF V & E COMPONENTS, INC.

720 West Fairfield Road – P.O. Box 7352 • High Point, North Carolina 27264 • Phone (910) 434-4109 • Fax (910) 434-2095

April 2, 2001

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**  
**7000 0600 0022 3964 2115**

Ms. Sharon Cihak  
Toxic & Health Hazard Specialist  
Guilford County Dept. of Environmental Health  
110 E. Wendover Ave.  
Greensboro, N.C. 27405



**RE: Site Closure Report**  
**6,000-Gallon, No. 2 Fuel Oil Underground Storage Tank (UST)**  
**2130 Brevard Road, High Point, Guilford County, North Carolina**

Dear Sharon:

Enclosed is the Site Closure report for the above referenced UST system located at the V&E Components – Brevard Road Facility. The UST had been utilized by prior owners to supply backup fuel (No. 2 fuel oil) to boilers used for comfort heat only. Although the UST is classified as unregulated, this report is being submitted to obtain “no further action required” documentation for the site. The tank was closed by removal and destruction per the NCDENR *December 2000 Guidelines for Tank Closure*.

Please review the enclosed report and forward a No Further Action Required letter to the address below:

Mr. Everette Vest  
President  
V&E Components, Inc.  
720 W. Fairfield Road  
High Point, N.C. 27264

Should you have any questions concerning report content, please call me at (336) 434-4109 or Doug Bensinger of Bensinger & Garrison Environmental, Inc. at (919) 484-8536.

Sincerely,  
**V&E COMPONENTS, INC.**

Everette Vest  
President

Enclosure

cc: Doug Bensinger, P.E. – B&G

## TABLE OF CONTENTS

### EXECUTIVE SUMMARY

#### A. GENERAL INFORMATION

#### B. SITE CLOSURE & INVESTIGATION PROCEDURES

#### C. CONCLUSIONS

#### D. RECOMMENDATION

#### E. CERTIFICATION

### TABLES

TABLE 1: SOIL SAMPLE ANALYTICAL RESULTS

TABLE 2: SOIL SAMPLE FIELD SCREENING RESULTS

### FIGURES

FIGURE 1: SITE LOCATION MAP

FIGURE 2: PROPERTY LAYOUT

### APPENDICES

APPENDIX I: NON-HAZARDOUS WASTE MANIFEST & TANK DISPOSAL  
MANIFEST

APPENDIX II: GW/UST-2 FORM, GW/UST-3 FORM, UST OPERATING PERMIT  
APPLICATION

APPENDIX III: TANK REMOVAL PERMIT

APPENDIX IV: ANALYTICAL REPORTS

APPENDIX V: PHOTOGRAPHS

APPENDIX VI: SITE SAFETY PLAN

## **EXECUTIVE SUMMARY**

On March 6, 2001, Bensinger & Garrison Environmental, Inc. (B&G) enlisted the services of OK Enterprises, Inc. to remove and dispose one 6,000-gallon, No. 2 fuel oil underground storage tank (UST) located at the V&E Components, Inc. Brevard Road Plant (see Figure 1: Site Location Map). The tank is unregulated per the NCAC Title 15A 2N .0280.12 definition of "underground storage tank". The tank location was on the west side of the main building, between the building and Brevard Road. Soil samples were taken in accordance with NCDENR Guidelines for Closure, however, to properly verify that a release had not occurred. Four soil samples were taken by B&G, one from beneath each end of the tank, one from beneath the parallel fuel oil supply lines, and one sample from beneath the parallel fuel oil return lines. All samples were taken less than two feet below the tank and fuel oil lines (see Figure 2: Property Layout). Soil sample analytical results indicated that no release had occurred from the tank. During field activities it was noted that no significant petroleum odors were detected in the soil, no free product was evident in the excavation pit, and the excavation was dry.

Prior to removal from the excavation, the tank was cleaned and all fuel oil sludge and cleaning water removed by vacuum hose. Once clear of the excavation, the tank was sealed, labeled, loaded, secured, and hauled off-site for destruction and recycling as scrap metal (see Non-Hazardous Waste Manifest and Tank Disposal Manifest in Appendix I).

### **A. GENERAL INFORMATION**

Site and tank information is found on Division of Water Quality (DWQ) forms GW/UST-2 and GW/UST-3 and the Division of Waste Management (DWM) Underground Storage Tank Operating Permit Application in Appendix II. The current tank owner, V&E Components, Inc., purchased the property from Carpenter Company in February 2000. Based on phone interviews with Carpenter Company personnel, the 6,000-gallon No. 2 fuel oil underground storage tank had not been filled for at least three years.

### **B. SITE CLOSURE AND INVESTIGATION PROCEDURES**

Ross Stitt, Tim Monroe, and Doug Bensinger of B&G arrived on the site the morning of 3/6/01 to commence closure activities. Prior to commencing work, the Site Safety Plan (see Appendix VI) was reviewed. NC One Call Center marked public utilities prior to 9 am and B&G personnel marked private utilities in close proximity to the UST. Prior to beginning excavation work, the location of geoprobe borings, installed by a separate environmental firm during an earlier phase II investigation, were marked and photographed (see Figure 2: Property Layout & Appendix V: Photograph Log). The High Point City Fire Inspector was then notified as required by the Tank Removal Permit (see Appendix III). Ms. Sharon Cihak of the Guilford County Department of Environmental Health was also notified of the scheduled tank removal in advance and arrived on site as initial excavation activities commenced. The NC Division of Waste Management (DWM) had been notified of the pending tank closure by submittal of "Notice of Intent" Form GW/UST-3 (see Appendix II).

OK Enterprises, subcontracted by B&G to remove and dispose of the tank, removed the fill pipe cap to verify that the tank was empty, then began excavation activities with removal of asphalt cover. The top of the tank was two feet below the paved surface. Total excavated area included a perimeter of approximately two feet, one-bucket width, around the tank. Three grab samples of soils excavated from above the tank, and in the vicinity of the fill pipe, were obtained by B&G and screened with a FID-OVA. None revealed evidence of petroleum contamination. Soil types observed within the excavation were predominantly red and brownish yellow silty clay loams of low permeability.

Once the tank was uncovered, OK Enterprises personnel disconnected supply, return, and vent piping. The tank was then tilted slightly to accommodate washing sludge to one end of the tank while residuals were removed from the other end with a vacuum hose (see Photograph Log in Appendix V). Approximately one hundred-fifty gallons of fuel oil sludge and water were collected for off site treatment and disposal. After cleaning and sludge removal, the tank was checked for explosive atmospheres. The reading inside the tank was <1% of the lower explosive limit (LEL).

After the tank was removed from the excavation, Tim Monroe and Ross Stitt collected soil samples from below each end of the tank profile and beneath the return and supply lines (see Figure 2: Property Layout). The fuel oil return and supply lines were all copper, run virtually side by side, and in excellent condition. Samples from beneath both systems, return (RL) and supply (SL), were obtained by hand auger within 2 feet of depth below the line. Tank pit samples, T1 and T2, were obtained from the backhoe bucket after excavating below the tank profile and measuring the depth to ensure the samples were within two feet of the pit bottom (see Photograph Log in Appendix V).

The tank pit was free of water and no visible sign of contamination was observed. Inspection of the tank shell did show some pitting (see Photograph Log in Appendix V); however, there was no indication tank integrity was compromised. Ms. Sharon Cihak, Toxic and Health Hazard Specialist for the Guilford County Department of Environmental Health, remained on site until all soil sampling was completed, the tank removed, labeled, loaded, and prepared for transport.

All soil samples were preserved on ice in the field and transported by chain of custody protocol to an EPA Drinking Water Certified Laboratory for analysis by Total Petroleum Hydrocarbons (TPH) Methods 3550 and 5030. Analytical results are shown in Table 1. Analytical reports are included in Appendix IV.

**TABLE 1**  
**SOIL SAMPLE ANALYTICAL RESULTS**

SAMPLE LOCATION	METHOD	RESULTS (mg/kg)
T1	5030 (TPH Low Fraction)	<1
	3550 (TPH High Fraction)	<10
T2	5030	<1
	3550	<10
RL	5030	<1
	3550	<10
SL	5030	<1
	3550	<10

Excess soil from each grab sample was screened in the field with a FID-OVA. Results are given in Table 2 below:

**TABLE 2**  
**SOIL SAMPLE FIELD SCREENING RESULTS**

SAMPLE LOCATION	DEPTH (FEET)	FID-OVA READING (ppm)
T1	11	0 (Initial)
		0 (15-minute)
T2	11.5	0 (Initial)
		0 (15-minute)
RL	2.5	0 (Initial)
		0 (15-minute)
SL	1.5	0 (Initial)
		0 (15-minute)

Once soil sampling was completed, the excavation was filled with both excavated soils and clean fill. Lifts were compacted by the backhoe bucket. Broken asphalt was loaded and transported off site for disposal. Crusher run stone was used for the final six inches of fill and to provide a crown to minimize potential infiltration of stormwater. Each lift of crusher run was compacted by rolling with multiple backhoe passes. Tim Monroe and Ross Stitt of B&G covered the former excavation area with 6-mil plastic sheeting (see Photograph Log in Appendix V).

### C. CONCLUSIONS

1. No release occurred from the UST system.
2. Although the tank shell did show signs of pitting, integrity of the steel tank was not compromised.
3. The geoprobe investigation conducted by others did not sample the tank at each end and geoprobe sample depths, approximately sixteen feet below grade, were four feet below the NCDENR recommended sampling depth for the tank.

#### D. RECOMMENDATION


1. B&G recommends that this report be submitted to the Guilford County Department of Environmental Health at the address below with a request that the department provide documentation of "No Further Action Required":

Ms. Sharon Cihak  
Toxic & Health Hazard Specialist  
Guilford County Dept. of Environmental Health  
110 E. Wendover Ave.  
Greensboro, N.C. 27405

#### E. CERTIFICATION

Bensinger and Garrison Environmental Inc. certifies that it has used standard and accepted practices in completion of this project. The undersigned (and their appointees) shall have no liability or obligation to any party other than V&E Components, Inc. (and its successors or assigns) and the undersigned's obligations (and their appointees') are limited to fraudulent statements herein made, or to negligence.


#### BENSINGER & GARRISON ENVIRONMENTAL, INC.



Tim W. Monroe  
Environmental Consultant

3-30-01


Date




Ross E. Stitt  
Environmental Scientist

3-30-01

Date

  
Douglas L. Bensinger, P.E.  
President/Senior Environmental Engineer  
Bluefield Engineering, P.C.




3/30/01

Date

# FIGURES





BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
BLUEFIELD ENGINEERING, P.C.



PROJECT NO. 1  
131401

DATE  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVM

FILE:  
VLE Bre. UST

SCALE:  
1"=2,000 ft

SOURCE:  
DeLorme 3D  
TopoQuads

USGS Topos  
High Point, NC

NOTES:

FIGURE 1: SITE LOCATION MAP  
V & E Components, Inc.

2130 Brevard Road  
High Point, Guilford Co., North Carolina






FIGURE 2: PROPERTY LAYOUT

V & E Components, Inc.  
2130 Brevard Road  
High Point, North Carolina

PROJECT NO.: 131401  
DATE: March 2001  
REVISION DATE: NA  
DRAWN BY: RES  
APPROVED BY: TWM  
FILE: V & E Bre. UST

SCALE: Not to Scale



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
BLUEFIELD ENGINEERING, P.C.

**APPENDIX I:**

**NON-HAZARDOUS WASTE MANIFEST  
AND  
TANK DISPOSAL MANIFEST**



OKEnterprises, Inc  
PO Box 41169  
Greensboro, NC 27404  
336-218-1090 O  
336-362-1703 M

## NON-HAZARDOUS WASTE MANIFEST

OKE Job #

Manifest #

306

Generator's Name and Mailing Address <i>VFE components 2130 Brevard Rd High Point North Carolina</i>	Site: Physical Location <i>same as manifest</i>	Owner of Contamination <i>W/A</i>
Generator's Phone #		Phone #

Project Name: *Bensinger & Garrison* Contact: *Chip Shi*

EPA ID #: *N/A* Job #: \_\_\_\_\_

Process which generated waste: *UST Removal*

I certify that the materials listed are properly described, classified, packaged, marked, and labeled, and are in proper condition to be transported in commerce under the applicable regulations of the State, the EPA, and the DOT. I certify that the waste described is non-hazardous and that the specific waste was delivered to the carrier named below for legal treatment, storage or disposal at the site indicated.

Signature: *[Signature]* Date: *3/6/01*

Description of Material	Qty./Form	Units	Vehicle #	Container Type
<i>Fuel oil</i>	Liquid <i>100</i>	<u>Gallons</u>	<i>95/307</i>	<u>Vacuum Tanker</u>
	Solid	Tons		Other
	Sludge <i>33</i>	Pounds		
	Total <i>133</i>	( ) Gal. Drums		

Transporter: OKEnterprises, Inc., PO Box 41169, Greensboro, NC 27404 Ph. 336-218-1090

EPA #: *N/A*

Vehicle License Tag #: *AJ*

Unit #: *95/317*

Container: Vacuum tanker

I certify that the specified waste was transferred in a registered (licensed) vehicle to the disposal treatment, storage, or disposal facility named below and was accepted.

*Quint Ocock*  
Printed Name

*Quint Ocock*  
Signature

*3/16/01*  
Date

Facility: <i>SHAMROCK CORP 6011 CORP PARK DR. BROWN SUMMIT NC</i>	Contact: <i>Jay</i>
Phone#	Approval:
Acknowledgement of receipt of waste materials covered in this manifest	
Printed Name	Signature
	Date

**OKEnterprises, Inc.**

PO Box 41169  
Greensboro, NC 27404  
336-218-1090 O  
336-362-1703 M

OKE Job #

## Tank Disposal Manifest

Tank Owner/Authorized Representative: Name & Mailing Address

2130 Brevard Rd  
High Point North Carolina

Tank Owner/Authorized Representative: *Behringer & Garrison Environmental*

Contact *Ch. P. M. Tim*

Phone # *919-484-8536*

Description of Tanks:

Tank #	Capacity	Previous Contents	Comments
<i>1</i>	<i>6000gal.</i>	<i>fuel oil</i>	

Tank Owner/Authorized Representative Certification:

The undersigned certifies that the above listed storage tank(s) have been removed from the premises of the tank owner.

*Tim Monroe*  
Name

*Tim Monroe*  
Signature

*3-6-01*  
Date

Transporter: The undersigned certifies that the above listed storage tank(s) have been transported to OKEnterprises, Inc., Greensboro, NC

*Quint Ocock*  
Signature

*3-6-01*  
Date

Disposal Certification: The undersigned certifies that the above named storage tank(s) have been cut into scrap pieces and accepted by Lee Iron & Metal, Hwy. 421 S. Sanford, NC.

*Quint Ocock*  
Signature

*3/13/01*  
Date

**APPENDIX II:**

**GW/UST-2 FORM**  
**GW/UST-3 FORM**  
**UST OPERATING PERMIT APPLICATION**



FOR  
TANKS  
IN  
NC

## Return Completed Form To:

The appropriate DWQ Regional Office according to the county of the facility's location.  
[SEE MAP ON REVERSE SIDE OF OWNER'S COPY (PINK) FOR REGIONAL  
OFFICE ADDRESS].

State Use Only

I.D. Number \_\_\_\_\_

Date Received \_\_\_\_\_

## INSTRUCTIONS

Complete and return within (30) days following completion of site investigation.

## I. Ownership of Tank(s)

Owner Name: V&amp;E Components, Inc.

Corporation, Individual, Public Agency, or Other Entity)

Street Address: 2130 Brevard Rd.

County: Guilford

City: High Point State: NC Zip Code: 27263

Telephone Number: ( 336 ) 434-4109

(Area Code)

## II. Location of Tank(s)

Facility Name: V&amp;E Components, Inc.

(or Company)

Facility ID # (if available):

Street Address 2130 Brevard Rd.

(or State Road)

County: Guilford City: High Point Zip Code: 27263

Telephone Number: ( 336 ) 434-4109

(Area Code)

## III. Contact Person

Name: Everette Vest

Job Title: Owner

Tel. No.: 336-434-4109

Closure Contractor: Bensinger &amp; Garrison Env. Address: PO Box 14609, RTP, NC 27709

Tel. No.: 919-484-8536

Primary Consultant: Doug Bensinger Address: PO Box 14609, RTP, NC 27709

Tel. No.: 919-484-8536

Lab: Chemical &amp; Environmental Technology Address: PO Box 12298, RTP, NC 27709

Tel. No.: 919-467-3090

## IV. U.S.T. Information

## V. Excavation Condition

## VI. Additional Information Required

Tank No.	Size in Gallons	Tank Dimensions	Last Contents	Water in Excavation		Free Product		Notable Odor or Visible Soil Contamination	
				Yes	No	Yes	No	Yes	No
1	6,000	8' x 16'	#2 fuel oil		X		X		X

See reverse side of pink copy (owner's copy) for additional information required by N.C. - DWQ in the written report and sketch.

**NOTE:** If a release from the tank(s) has occurred, the site assessment portion of the tank closure must be conducted under the supervision of a P.E. or L.G., with all closure site assessment reports bearing the signature and seal of the P.E. or L.G.

## VII. Check List (Check the activities completed)

## PERMANENT CLOSURE (For Removing or Abandoning-In-place)

- ☒ Contact local fire marshal.  
☒ Notify DWQ Regional Office before abandonment.  
☒ Drain & flush piping into tank.  
☒ Remove all product and residuals from tank.  
☒ Excavate down to tank.  
☒ Clean and inspect tank.  
☒ Remove drop tube, fill pipe, gauge pipe, vapor recovery tank connections, submersible pumps and other tank fixtures.  
☒ Cap or plug all lines except the vent and fill lines.  
☒ Purge tank of all product & flammable vapors.  
☒ Cut one or more large holes in the tanks.  
☒ Backfill the area.  
Date Tank(s) Permanently closed: 3-6-01  
Date of Change-in-Service: \_\_\_\_\_

## ABANDONMENT IN PLACE

- ☐ Fill tank until material overflows tank opening.  
☐ Plug or cap all openings.  
☐ Disconnect and cap or remove vent line.  
☐ Solid inert material used - specify: \_\_\_\_\_

## REMOVAL

- ☒ Create vent hole.  
☒ Label tank.  
☒ Dispose of tank in approved manner. Lee Iron & Metal  
Final tank destination: Hwy 421 S., Sanford, NC


## VIII. Certification (Read and Sign)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete.

Print name and official title of owner or owner's authorized representative

Everette Vest

Signature



Date Signed

4-4-01

North Carolina  
Department of Environment and Natural Resources

Michael F. Easley, Governor  
William G. Ross Jr., Secretary



Division of Waste Management  
UST Section

February 28, 2001

V & E Components, Inc.  
Attn: Everette Vest, Owner  
2130 Brevard Road  
High Point, NC 27263

Dear Mr. Vest:

This letter is to acknowledge your Notification of Tank Closure as received **February 22, 2001**, and filed as **V & E Components, Inc.** All future correspondence must contain the file name as well as an address and county in the subject to ensure its receipt into our filing system.

Please be advised that work performed which involves site assessment or any work requiring detail technical knowledge of site conditions, should be performed by persons, firms, or professional corporations who are duly licensed to offer geological or engineering services by the appropriate occupational licensing board. For regulated tanks, the results of the required assessment (NCAC Title 15A Subchapter 2N Section .0803) should be submitted to this office no later than thirty (30) days after the tank is closed. If there is evidence of a release or suspected release, it must be reported within twenty-four (24) hours.

Also, please remember that to permanently close a tank, owners and operators must empty and clean it by removing all liquids and accumulated sludges as required under 15A 2N .0802.

If a specific date for tank closure was not noted on the UST-3 form, then a specific date must be given 5 - 7 working days prior to tank closure. Underground Storage Tank (UST) staff will be conducting random site visits to insure that underground storage tank closures are conducted as required by 15A NCAC 2N .0802 and .0803. Any violations documented may be submitted for enforcement action.

Enclosed is an attachment that is to be used for the information required for closure assessment. Please contact Sharon Cihak at (336) 373-3771, if you have any questions concerning these requirements.

Sincerely,

*Alice Lunsford*  
Cindy H. Rintoul  
UST Regional Supervisor

Enclosure

cc: WSRO  
Guilford County Fire Marshall

~~Carrington & Garrison Environmental, Inc.~~

Winston-Salem Regional Office, 585 Waughtown Street, Winston-Salem, North Carolina 27107-2241

Phone: 336 - 771-4600 \ FAX: 336 - 771-4632 \ Internet: [www.enr.state.nc.us/ENR/](http://www.enr.state.nc.us/ENR/)

GW/UST-3

## Notice of Intent: UST Permanent Closure or Change-In-Service

FOR  
TANKS  
IN  
NC

## Return Completed Form To:

The appropriate DWQ Regional Office according to the county of the facility's location. [SEE REVERSE SIDE OF OWNER'S COPY (PINK) FOR REGIONAL OFFICE ADDRESS].

State Use Only

I. D. Number \_\_\_\_\_

Date Received \_\_\_\_\_

## INSTRUCTIONS

Complete and return at least five (5) working days prior to closure or change-in-service if a Professional Engineer (P.E.) or a Licensed Geologist (L.G.) provides supervision for closure or change-in-service site assessment activities and signs and seals all closure reports. Otherwise, thirty (30) days notice is required.

## I. OWNERSHIP OF TANK(S)

Tank Owner Name: V&E Components, Inc.

(Corporation, Individual, Public Agency, or Other Entity)

Street Address: 2130 Brevard Rd.County: GuilfordCity: High Point State: NC Zip Code: 27263Tele. No. (Area Code): (336) 434-4109

## II. LOCATION OF TANK(S)

Facility Name or Company: V&E Components, Inc.

Facility ID # (if available): \_\_\_\_\_

Street Address or State Road: 2130 Brevard Rd.County: Guilford City: High Point Zip Code: 27263Tele. No. (Area Code): (336) 434-4109

## III. CONTACT PERSON

Name: Everette VestJob Title: OwnerTelephone Number: (336) 434-4109

## IV. TANK REMOVAL, CLOSURE IN PLACE, CHANGE-IN-SERVICE

1. Contact Local Fire Marshall.
2. Plan the entire closure event.
3. Conduct Site Soil Assessments.
4. If Removing Tanks or Closing in Place refer to API Publications 2015 "Cleaning Petroleum Storage Tanks" & 1604 "Removal & Disposal of Used Under-ground Petroleum Storage Tanks".

5. Provide a sketch locating piping, tanks and soil sampling locations.
6. Submit a closure report in the format of GW/UST-12 and include the form GW/UST-2 within 30 days following the site investigation.
7. If a release from the tank(s) has occurred, the site assessment portion of the tank

- closure must be conducted under the supervision of a P.E. or L.G., with all closure site assessment reports bearing signature and seal of the P.E. or L.G. If a release has not occurred, the supervision, signature, or seal of a P.E. or L.G. is not required.
8. Keep closure records for 3 years.

## V. WORK TO BE PERFORMED BY:

(Contractor) Name: Bensinger & Garrison Environmental, Inc.Address: PO Box 14609, Research Triangle Park State: NCZip Code: 27709Contact: Doug Bensinger, PEPhone: (919) 484-8536Primary Consultant: Doug Bensinger, PEPhone: (919) 484-8536

## VI. TANK(S) SCHEDULED FOR CLOSURE OR CHANGE-IN-SERVICE

TANK ID#	TANK CAPACITY	LAST CONTENTS	PROPOSED ACTIVITY		
			CLOSURE		CHANGE-IN-SERVICE
			Removal	Abandonment In Place	New Contents Stored
1	6,000 gal.	No. 2 fuel oil	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	

## VII. OWNER OR OWNER'S AUTHORIZED REPRESENTATIVE

Print name and official title

Doug Bensinger, PE\*Scheduled Removal Date: 3/6/01Signature: *Doug Bensinger*Date Submitted: 2/20/01

\*If scheduled work date changes, notify your appropriate DWQ Regional Office 48 hours prior to originally scheduled date.



ARPENTER Comfort Cushioning  
Products



Certified Mail Item # 7099 3400 0007 6460 6364  
Return Receipt Requested

November 13, 2000

W and D Properties  
1022 Porter Street  
High Point, NC 27262

To Whom It May Concern :

Enclosed please find the forms for reporting an unregulated underground tank and paying the fees associated with its operation. This is for the underground heating oil tank located at 2130 Brevard Road in High Point which was sold by Carpenter Co. to W and D Properties in February of this year. We are doing this per instructions from the NCDENR, Division of Waste Management - UST Section and have sent copies of all letters and paperwork to them, including a copy of the North Carolina General Warranty Deed. If you have any questions please contact the UST Section in Raleigh for clarification.

Sincerely,

Ray Ritchie  
Environmental Coordinator  
Conover Division

(Enclosure)

PC: Rodney Gilbert  
Gary Gilliam  
Will Robin

CARPENTER CO.  
2069 KEISLER DAIRY ROAD  
P. O. BOX 879  
CONOVER, NORTH CAROLINA 28613  
828 464.9470

We bring comfort to your life.<sup>SM</sup>

11/20 00 15:07 NO.300 02/04

336 4342095

V8E COMPONENTS

NCDENR  
Division of Waste  
Management UST Section

# Underground Storage Tank Operating Permit Application

Complete the questionnaire on the  
reverse side and return it with proper  
fee payment to:  
DENR-UST, 1646 Mail Service Center  
Raleigh, NC 27689-1646  
Attn: DWM UST Section

NOV - 6 REC'D

CARPENTER COMPANY  
2009 KEISLER RD, P.O. BOX 879  
CONOVER  
NC 28613-0879

UST FACILITY ID #: 0-027281  
CARPENTER COMPANY  
2130 BREVARD RD & PO BOX 1370  
HIGH POINT NC 27261 828  
UST OWNER TEL. #: (704) 464-9470

TANK #	CAPACITY (GALS)	CONTENTS	INSTALLATION DATE
01	68,000.00	Fuel Oil	1961/01/01

If the above information is not correct or is incomplete, please make the corrections  
on this application and submit the required documentation (see "Step One" on Page 4).

## PART A

VOLUME of TANK (GALLONS)	NUMBER of TANKS WITH PRODUCT		TOTAL NUMBER of TANKS	TANK FEE RATE	ANNUALLY or QUARTERLY AMOUNT DUE	PERIOD of COVERAGE
	(A)	(B)				
greater than 3,500	0	1	1	X	\$300.00 per	FROM:
3,500 or less	0	0	0	X	\$200.00 per	01/01/01
LAST PAYMENT RECEIVED: 11/23/99			PRORATED FEES (SEE INSTRUCTIONS)		(4) = .00	THROUGH: 12/31/01
DATE LAST BILLED: 11/01/99			RETROACTIVE FEES (SEE INSTRUCTIONS)		(5) = .00	
BILLING DATE: 11/01/00			LATE PENALTY		(6) = .00	
DUE DATE: 12/01/00			TOTAL PAYMENT DUE (1)+(2)+(3)+(4)+(5)+(6) =		300.00	
<input type="checkbox"/> Check here for an ownership change.				Previous Owner:	Current Owner:	

**APPENDIX III:**  
**TANK REMOVAL PERMIT**



## HIGH POINT FIRE DEPARTMENT

## TANK REMOVAL PERMIT

Application is hereby made by the undersigned for permission to:

X

Remove Tank(s)

Abandon Tank(s) in or on the premises known as:

U+E Components, Inc 2130 Brevard Rd  
(Name and Address of Business) High Point, NC

1. Name of Contractor: Bensinger + Garrison Env. Inc.  
Address of Contractor: PO Box 14609  
Research Triangle Park, NC 27709
- Number of Tanks to be Disposed of: One
- Size of Tanks: 6,000 gallon
- Tanks Contain: #2 fuel oil for heating
- Where Tanks Located: in the parking area between the building and Brevard Rd
2. All permits shall be obtained prior to the work being started and also shall remain on site until the completion of same.
3. All work shall comply with the governing regulations such as: NFPA 327, Guilford County Environmental Health Department, and Volume V- Chapter Nine of the State Building Code.
4. Both Guilford County Toxic and Health (574-3540) and High Point Fire Department (883-3364) shall be notified prior to the beginning of such work.
5. Before any tank(s) can be removed they must be rendered inert of flammable vapors. All purging or inerting shall be conducted in accordance with applicable standards and regulations. For purging, the vapors shall remain below 20% of the lower flammable limit. For inerting, the oxygen level shall be below 8%. The

FEB-26-01 MON 10:25

HIGH POINT FIRE DEPT

FAX NO. 3368833550

P. 03

02/14/2001 WED 16:23 FAX

JAN-02-01 TUE 13:10

HIGH POINT FIRE DEPT

FAX NO. 3368833550

P. 03

contractor will be responsible for making sure that all monitoring equipment is kept on site along with qualified personnel to operate same.

6. Tank(s) which have been removed from the ground shall be taken to be disposed of within the same day of removal. All tanks shall be marked with legible letters at least two (2) inches high with the following lettering:

**TANK HAS CONTAINED LEADED GASOLINE  
NOT VAPOR FREE  
NOT SUITABLE FOR STORAGE OF FOOD FOR HUMAN OR  
ANIMAL CONSUMPTION  
DATE OF REMOVAL: MONTH/DAY/YEAR**

7. Tanks to be transported in accordance with all applicable Local, State, and Federal regulations. Tanks opening to be plugged or capped with one plug having a 1/8 inch vent hole to prevent the tanks from being subjected to excessive differential pressure. Tanks to be secured on a truck for transportation to the storage or disposal site with the 1/8 inch vent hole located at the uppermost point of the tank.
8. Contractor shall complete and submit to the Guilford County Environmental Health and High Point Fire Department, copies of the disposal and soil test results.
9. Removal or abandonment of tank(s) without obtaining required permits and proper compliance with applicable regulations is punishable by law.

I understand and consent to the above stipulated conditions upon which this permit is granted. Failure to obtain permit and comply with regulations may render you liable to the penalties provided by law.

Bensinger + Garrison Env. Inc.  
Applicant

2/14/01  
Date

Phone: Day: (919) 484-8536  
Night: (919) 481-4720  
(919) 481-2530

Donald L. Hinchman  
Fire Inspector

FEB 26, 2001  
Date

Permit: Granted: X  
Denied: \_\_\_\_\_

01/02/2001 TUE 13:05

[TX/RX NO 8043] 003

# **APPENDIX IV:**

## **ANALYTICAL REPORTS**



# CHEMICAL & ENVIRONMENTAL TECHNOLOGY, INC.

## ENVIRONMENTAL ANALYTICAL SERVICES

### FINAL REPORT OF ANALYSES

BENSINGER & GARRISON  
PO BOX 14609  
RTP, NC 27709-  
Attn: ROSS STITT

REPORT DATE: 03/09/01

131401

SAMPLE NUMBER- 182090 SAMPLE ID- T1  
DATE SAMPLED- 03/06/01  
DATE RECEIVED- 03/07/01 SAMPLER- ROSS STITT  
TIME RECEIVED- 0950 DELIVERED BY- RON STITT

SAMPLE MATRIX- SO  
TIME SAMPLED- 1220  
RECEIVED BY- SMC

Page 1 of 1

PROJECT NAME : 131401

ANALYSIS	METHOD	SAMPLE PREP DATE	ANALYSIS BY DATE	BY	RESULT UNITS	PQL
PERCENT SOLIDS	2540G		03/07/01	SMC	74.1 NA	
HIGH FRACTION HYDROCARBON	3550	03/07/01	JBR	03/07/01	JBR	< 10.0 mg/kg 10.0
LOW FRACTION HYDROCARBON	5030		03/07/01	JBR	< 1.00 mg/kg	1.00

PQL = Practical Quantitation Limit

Results followed by the letter J are estimated concentrations.

All results for soil and sludge samples are reported on a dry weight basis as required by the NC DEM Laboratory Certification Section. Wet Weight Concentration = (dry weight conc.)(percent solids)/100.

LOW FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE GASOLINE RANGE (GRO).

HIGH FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE DIESEL RANGE (DRO).

NC DENR CERTIFICATIONS: DWQ - 96; PUBLIC WATER SUPPLY - 37724

LABORATORY DIRECTOR



# CHEMICAL & ENVIRONMENTAL TECHNOLOGY, INC.

## ENVIRONMENTAL ANALYTICAL SERVICES

### FINAL REPORT OF ANALYSES

BENSINGER & GARRISON  
PO BOX 14609  
RTP, NC 27709-  
Attn: ROSS STITT

REPORT DATE: 03/09/01

131401

SAMPLE NUMBER- 182091 SAMPLE ID- T2  
DATE SAMPLED- 03/06/01  
DATE RECEIVED- 03/07/01 SAMPLER- ROSS STITT  
TIME RECEIVED- 0950 DELIVERED BY- RON STITT

SAMPLE MATRIX- SO  
TIME SAMPLED- 1235  
RECEIVED BY- SMC

Page 1 of 1

PROJECT NAME : 131401

ANALYSIS	METHOD	SAMPLE PREP DATE	ANALYSIS BY DATE	BY	RESULT UNITS	PQL
PERCENT SOLIDS	2540G		03/07/01	SMC	80.1 NA	
HIGH FRACTION HYDROCARBON	3550	03/07/01	JBR	03/07/01	JBR	< 10.0 mg/kg 10.0
LOW FRACTION HYDROCARBON	5030		03/07/01	JBR	< 1.00 mg/kg	1.00

PQL = Practical Quantitation Limit

Results followed by the letter J are estimated concentrations.

All results for soil and sludge samples are reported on a dry weight basis as required by the NC DEM Laboratory Certification Section. Wet Weight Concentration = (dry weight conc.)(percent solids)/100.

LOW FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE GASOLINE RANGE (GRO).

HIGH FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE DIESEL RANGE (DRO).

NC DENR CERTIFICATIONS: DWQ - 96; PUBLIC WATER SUPPLY - 37724

LABORATORY DIRECTOR





# CHEMICAL & ENVIRONMENTAL TECHNOLOGY, INC.

## ENVIRONMENTAL ANALYTICAL SERVICES

### FINAL REPORT OF ANALYSES

BENSINGER & GARRISON  
PO BOX 14609  
RTP, NC 27709-  
Attn: ROSS STITT

REPORT DATE: 03/09/01

131401

SAMPLE NUMBER- 182092 SAMPLE ID- SL  
DATE SAMPLED- 03/06/01  
DATE RECEIVED- 03/07/01 SAMPLER- ROSS STITT  
TIME RECEIVED- 0950 DELIVERED BY- ROSS STITT

SAMPLE MATRIX- SO  
TIME SAMPLED- 1230  
RECEIVED BY- SMC

Page 1 of 1

PROJECT NAME : 131401

ANALYSIS	METHOD	SAMPLE PREP DATE	ANALYSIS BY DATE	BY	RESULT UNITS	PQL
PERCENT SOLIDS	2540G		03/07/01	SMC	80.6 NA	
HIGH FRACTION HYDROCARBON	3550	03/07/01	JBR	03/07/01	JBR	< 10.0 mg/kg 10.0
LOW FRACTION HYDROCARBON	5030		03/07/01	JBR	< 1.00 mg/kg	1.00

PQL = Practical Quantitation Limit

Results followed by the letter J are estimated concentrations.


All results for soil and sludge samples are reported on a dry weight basis as required by the NC DEM Laboratory Certification Section. Wet Weight Concentration = (dry weight conc.)(percent solids)/100.

LOW FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE GASOLINE RANGE (GRO).

HIGH FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE DIESEL RANGE (DRO).

NC DENR CERTIFICATIONS: DWQ - 96; PUBLIC WATER SUPPLY - 37724

LABORATORY DIRECTOR



# CHEMICAL & ENVIRONMENTAL TECHNOLOGY, INC.

## ENVIRONMENTAL ANALYTICAL SERVICES

### FINAL REPORT OF ANALYSES

BENSINGER & GARRISON  
PO BOX 14609  
RTP, NC 27709-  
Attn: ROSS STITT

REPORT DATE: 03/09/01

131401

SAMPLE NUMBER- 182093 SAMPLE ID- RL  
DATE SAMPLED- 03/06/01  
DATE RECEIVED- 03/07/01 SAMPLER- ROSS STITT  
TIME RECEIVED- 0950 DELIVERED BY- ROSS STITT

SAMPLE MATRIX- SO  
TIME SAMPLED- 1240  
RECEIVED BY- SMC

Page 1 of 1

PROJECT NAME : 131401

ANALYSIS	METHOD	SAMPLE PREP DATE	ANALYSIS BY DATE	BY	RESULT UNITS	PQL
PERCENT SOLIDS	2540G		03/07/01	SMC	84.3 NA	
HIGH FRACTION HYDROCARBON	3550	03/07/01	JBR	03/07/01	JBR	< 10.0 mg/kg 10.0
LOW FRACTION HYDROCARBON	5030		03/07/01	JBR	< 1.00 mg/kg	1.00

PQL = Practical Quantitation Limit

Results followed by the letter J are estimated concentrations.


All results for soil and sludge samples are reported on a dry weight basis as required by the NC DEM Laboratory Certification Section. Wet Weight Concentration = (dry weight conc.)(percent solids)/100.

LOW FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE GASOLINE RANGE (GRO).

HIGH FRACTION HYDROCARBON RESULT REFLECTS THE SUM OF ALL COMPOUNDS IN THE DIESEL RANGE (DRO).

NC DENR CERTIFICATIONS: DWQ - 96; PUBLIC WATER SUPPLY - 37724

LABORATORY DIRECTOR





## CHAIN OF CUSTODY

[illegible]

**\*Rush work requires laboratory approval prior to sample submission. Additional charges may apply.**

**REFERENCES**

**Wastewater Program References (Includes Groundwater and Solids)**

**"Rules Governing Laboratory Certification" NCAC, Title 15 DENR, Chapter 2H .0800, February 2, 1994**

North Carolina Administrative Code for Wastewater Laboratories

**Federal Register, 40 CFR Part 136, July 1, 1998**

Metals, Inorganics, and Organics for groundwater and wastewater sampling, preservation, and analysis

**Groundwater Section Guidelines for the Investigation and Remediation of Soils and Groundwater, Volumes I and II, May and January 1998, Respectively**

Required Methodology for Groundwater and Soil Remediation and Assessment (UST and Non-UST).

**Method for the Determination of Volatile Petroleum Hydrocarbons (VPH), MADEP, January 1998**

VPH Method

**Method for the Determination of Extractable Petroleum Hydrocarbons (EPH), MADEP, January 1998**

EPH Method

**Guidelines for Site Assessment, cleanup, and UST Closure, State of California Leaking UST Task Force, Appendix D, October 1989**

TPH Method for TPH GRO and DRO

**SW - 846, Third Edition, Final Update III, June 1997**

Inorganics and Organics in soil or sludges. Hazardous Waste. TCLP for Solid and Liquid Waste. Metals in soil, sludge, or groundwater. (Metals analyses for NC groundwater compliance are digested by Method 3030C, Standard Methods, 18<sup>th</sup> Edition.)

**Drinking Water Program References**

**"Laboratory Certification" NCAC, Title 15A DHHS, 20D.0200, January 26, 1996**

North Carolina Administrative Code for Drinking Water Laboratories

**"Rules Governing Public Water Systems" DENR, Division of Environmental Health, Public Water Supply Section, October, 1997 Printing**

North Carolina Administrative Code for required Methods and Sampling for Public Water Systems

**Federal Register, 40 CFR Parts 141-143, July 1, 1998**

**Metals, Inorganics, and Organics for drinking water sampling, preservation, and analysis**

**"Technical Notes on Drinking Water Methods" USEPA, EMSL, EPA-600/R-94-173, October 1994 (NTIS PB95-104766)**

**General guidance and notes regarding updates for acceptable methods and practices**

**"Methods for the Determination of Metals in Environmental Samples-Supplement I" USEPA ORD, EPA-600/R-94/111, May 1994 (NTIS PB95-125472)**

**"Methods for the Determination of Organic Compounds in Drinking Water", USEPA, EPA-600/4-88-039, December, 1980, Revised July 1991**

**References Supporting Wastewater and Drinking Water Programs**

**"Methods for Chemical Analysis of Water and Wastes", USEPA  
EPA-600/4-79-020, March 1983**

**Inorganics and wet chemistry analyses for wastewater, groundwater, and drinking water**

**"Standard Methods", 18<sup>th</sup> Edition, 1992**

**Inorganics, Metals, Organics, Total & Fecal Coliform (and Strep) for groundwater, wastewater, stream samples, and drinking water**

**"Method 504.1 1,2-Dibromoethane (EDB), 1,2 Dibromo-3-Chloropropane (DBCP), and 1,2,3-trichloropropane (123 TCP) in water by Microextraction and GC, Rev 1.1 USEPA, ORD 1995**

**Wastewater and Drinking Water**

# **APPENDIX V: PHOTOGRAPHS**





Geoprobe and Tank Fill Pipe Locations



View of the Tank and Geoprobe Alignment



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO. 1  
131481

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVH

FILE:  
V & E Bre. UST

SCALE:  
Not to Scale

NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina



Sludge Removal



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO.:  
131401

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVH

FILE:  
V & E Bre. LIST

SCALE:  
Not to Scale

NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina





Tank Cleaning



Check for Combustible Vapors (Reading of 1% LEL)



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO. 1  
131401

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVH

FILE:  
V & E Bre. UST

SCALE:  
Not to Scale

NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina



Bottom of the Tank



Surface Pitting of the Steel Tank (Note Shell is not Breached)



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO. 1  
131401

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVH


FILE:  
V & E Bre. UST

SCALE:  
Not to Scale

NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina



Bottom of the Tank Pit (No Visible Sign of a Leak)



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO. :  
131401

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVH


FILE:  
V & E Bre. UST

SCALE:  
Not to Scale

NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina



Measurement for Sample Depth



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO. 1  
131401

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVM

FILE:  
V & E Bre. LST

SCALE:  
Not to Scale


NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina



Backfilling the Excavation



Completed Fill with 6 Inches of Crush and Run Gravel

B&G

BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO. :  
131401

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVM

FILE:  
V & E Bre. UST

SCALE:  
Not to Scale

NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina



Site Temporary Cover



BENSINGER & GARRISON  
ENVIRONMENTAL, INC.  
Bluefield Engineering, P.C.



PROJECT NO.:  
131401

DATE:  
March, 2001

DRAWN BY:  
RES

APPROVED BY:  
TVM

FILE:  
V & E Bre. UST

SCALE:  
Not to Scale

NOTES:

PHOTOGRAPHIC LOG  
V & E Components, Inc.

2130 Brevard Road  
High Point, North Carolina

**APPENDIX VI:**  
**SITE SAFETY PLAN**



Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN  
29CFR 1910.120(b)(1)(ii)(C) Project No. 131401

This appendix provides a generic plan based on a plan developed by the U.S. Coast Guard for responding to hazardous chemical releases.<sup>1</sup> This generic plan can be adapted for designing a Site Safety Plan for hazardous waste site cleanup operations. It is not all inclusive and should only be used as a guide, not a standard. This plan should be kept on-site.

A. SITE DESCRIPTION

Date \_\_\_\_\_ Location 2130 Brevard Rd High Point, NC  
Hazards #2 fuel oil UST  
Area affected UST location  
Surrounding population Commercial / Industrial  
Topography hilly  
Weather conditions \_\_\_\_\_

Additional information \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

- B. ENTRY OBJECTIVES - The objective of the initial entry to the contaminated area is to (describes actions, tasks to be accomplished; i.e., identify contaminated soil; monitor conditions, etc.)

remove one 6,000 gal #2 fuel oil UST

- C. ONSITE ORGANIZATION AND COORDINATION - The following personnel are designated to carry out the stated job functions on site. (Note: One person may carry out more than one job function.)

PROJECT TEAM LEADER \_\_\_\_\_

SCIENTIFIC ADVISOR \_\_\_\_\_

SITE SAFETY OFFICER \_\_\_\_\_

PUBLIC INFORMATION OFFICER \_\_\_\_\_

SECURITY OFFICER \_\_\_\_\_

RECORDKEEPER \_\_\_\_\_

FINANCIAL OFFICER \_\_\_\_\_

FIELD TEAM LEADER \_\_\_\_\_

FIELD TEAM MEMBERS \_\_\_\_\_

Chip Stitt Tim Monroe

<sup>1</sup>U.S. Coast Guard. Policy Guidance for Response to Hazardous Chemical Releases. USCG Pollution Response COMDTINST-M16465.30.



# Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

FEDERAL AGENCY REPS (i.e., EPA, NIOSH)

STATE AGENCY REPS

LOCAL AGENCY REPS

CONTRACTOR(S)

OK Enterprises

All personnel arriving or departing the site should log in and out with the Recordkeeper. All activities on site must be cleared through the Project Team Leader.

## D. ONSITE CONTROL

U+E Components, Inc. and Bensinger + Garrison  
(Name of individual or agency) has been designated to coordinate access control and security on site. A safe perimeter has been established at (distance or description of controlled area) 50 ft from the  
vacant site

No unauthorized person should be within this area.

The onsite Command Post and staging area have been established at the Bensinger + Garrison service vehicle

The prevailing wind conditions are \_\_\_\_\_. This location is upwind from the Exclusion Zone.

Control boundaries have been established, and the Exclusion Zone (the contaminated area), hotline, Contamination Reduction Zone, and Support Zone (clean area) have been identified and designated as follows: (describe boundaries and/or attach map of controlled area)

These boundaries are identified by: (marking of zones, i.e., red boundary tape - hotline; traffic cones - Support Zone; etc.)

# Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

## E. HAZARD EVALUATION

The following substance(s) are known or suspected to be on site. The primary hazards of each are identified.

<u>Substances Involved</u> (chemical name)	<u>Concentrations (If Known)</u>	<u>Primary Hazards</u> (e.g., toxic on inhalation)
<u>#2 fuel oil</u>		<u>inhalation</u>

The following additional hazards are expected on site: (i.e., slippery ground, uneven terrain, etc.) pit area will be open

Hazardous substance information form(s) for the involved substance(s) have been completed and are attached.

## F. PERSONAL PROTECTIVE EQUIPMENT

Based on evaluation of potential hazards, the following levels of personal protection have been designated for the applicable work areas or tasks:

<u>Location</u>	<u>Job-Function</u>	<u>Level of Protection</u>				
Exclusion Zone	<u>UST removal</u> <u>(6000 gal #2 fuel oil)</u>	A	B	C	<u>(D)</u>	Other
		A	B	C	D	Other
		A	B	C	D	Other
		A	B	C	D	Other
Contamination Reduction Zone		A	B	C	D	Other
		A	B	C	D	Other
		A	B	C	D	Other
		A	B	C	D	Other

Specific protective equipment for each level of protection is as follows:

Level A	<u>Fully-encapsulating suit</u> <u>SCBA</u> <u>(disposable coveralls)</u>	Level C	<u>Splash gear (type)</u> <u>Full-face canister resp.</u>
Level B	<u>Splash gear (type)</u> <u>SCBA</u>	Level D	<u>hard hat, steel toe boots,</u> <u>gloves for sampling</u>
Other			

# Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

The following protective clothing materials are required for the involved substances:

<u>Substance</u>	<u>Material</u>
(chemical name)	(material name, e.g., Viton)
_____	_____
_____	_____
_____	_____
_____	_____

If air-purifying respirators are authorized, (filtering medium) is the appropriate canister for use with the involved substances and concentrations. A competent individual has determined that all criteria for using this type of respiratory protection have been met.

NO CHANGES TO THE SPECIFIED LEVELS OF PROTECTION SHALL BE MADE WITHOUT THE APPROVAL OF THE SITE SAFETY OFFICER AND THE PROJECT TEAM LEADER.

## G. ONSITE WORK PLANS

Work party(s) consisting of \_\_\_\_\_ persons will perform the following tasks:

<u>Project Team Leader</u>	<u>Tim Monal</u> (name) <u>Chip Stolt</u>	(function)
		<u>Supervise UST removal</u> <u>and take soil samples</u>
<u>Work Party #1</u>	<u>Bensinger +</u> <u>Garrison Env.</u>	<u>11.</u>
<u>Work Party #2</u>	<u>OK Enterprises</u>	<u>remove UST from ground;</u> <u>backfill pit; remove UST from</u> <u>site and dispose of UST;</u> <u>dispose of UST contents</u>
<u>Rescue Team</u> (required for entries to IDLE environments)	_____	_____
<u>Decontamination</u> <u>Team</u>	_____	_____

The work party(s) were briefed on the contents of this plan at \_\_\_\_\_.

## H. COMMUNICATION PROCEDURES

Channel \_\_\_\_\_ has been designated as the radio frequency for personnel in the Exclusion Zone. All other onsite communications will use channel \_\_\_\_\_.

Personnel in the Exclusion Zone should remain in constant radio communication or within sight of the Project Team Leader. Any failure of radio communication requires an evaluation of whether personnel should leave the Exclusion Zone.

(Horn blast, siren, etc.) is the emergency signal to indicate that all personnel should leave the Exclusion Zone. In addition, a loud hailer is available if required.

The following standard hand signals will be used in case of failure of radio communications:

Hand gripping throat _____	Out of air, can't breathe
Grip partner's wrist or _____ both hands around waist	Leave area immediately
Hands on top of head _____	Need assistance
Thumbs up _____	OK, I am all right, I understand
Thumbs down _____	No, negative

Telephone communication to the Command Post should be established as soon as practicable. The phone number is (919) 484-8536 office

## I. DECONTAMINATION PROCEDURES

cell phone at the site 349-8089  
522-9077

Personnel and equipment leaving the Exclusion Zone shall be thoroughly decontaminated. The standard level \_\_\_\_\_ decontamination protocol shall be used with the following decontamination stations: (1) \_\_\_\_\_

(2) _____	(3) _____	(4) _____	(5) _____
(6) _____	(7) _____	(8) _____	(9) _____
(10) _____	Other _____		

Emergency decontamination will include the following stations: \_\_\_\_\_

pool and water at the site

The following decontamination equipment is required: \_\_\_\_\_

(Normally detergent and water) will be used as the decontamination solution.

## J. SITE SAFETY AND HEALTH PLAN

Chip Stitt / Tim Monroe  
1. (name) is the designated Site Safety Officer and is directly responsible to the Project Team Leader for safety recommendations on site.

# Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

## 2. Emergency Medical Care

High Point  
Regional  
Hospital

(names of qualified personnel) \_\_\_\_\_ are the qualified EMTs on site.  
(medical facility names) \_\_\_\_\_, at (address) 601 N. Elm St High Point, NC  
phone \_\_\_\_\_ is located 15 minutes from this location.  
(name of person) \_\_\_\_\_ was contacted at (time) \_\_\_\_\_ and briefed on  
the situation, the potential hazards, and the substances involved. A map  
of alternative routes to this facility is available at (normally Command  
Post) \_\_\_\_\_.

Local ambulance service is available from 911 High Point Regional Hospital at  
phone (336) 884-6009. Their response time is 15 minutes.  
Whenever possible, arrangements should be made for onsite standby.

First-aid equipment is available on site at the following locations:

First-aid kit  
Emergency eye wash  
Emergency shower  
(other) \_\_\_\_\_

Bensinger + Garrison service vehicle  
\_\_\_\_\_  
\_\_\_\_\_

Emergency medical information for substances present:

Substance	Exposure Symptoms	First-Aid Instructions
# <u>2 fuel oil</u>	<u>headache, dizziness</u> <u>vertigo</u>	<u>remove from area</u>
_____	_____	_____
_____	_____	_____
_____	_____	_____

List of emergency phone numbers: 911

Agency/Facility	Phone #	Contact
Police <u>911</u>	<u>(336) 883-3224</u>	
Fire <u>911</u>	<u>(336) 883-3374</u>	
Hospital <u>911 High Point Regional Hospital</u>	<u>(336) 884-8400</u>	<u>(Emergency) (336) 884-6009</u>
Airport <u>Piedmont Triad Airport</u>	<u>(336) 665-5600</u>	
Public Health Advisor <u>Guilford County Health Dept</u>	<u>574-3540</u>	

Directions to Hospital: Left on Fecley, Right on Sublett, Right on Elm, Hospital on Left.

## 3. Environmental Monitoring

The following environmental monitoring instruments shall be used on site  
(cross out if not applicable) at the specified intervals.

Combustible Gas Indicator	- continuous/hourly/daily/other _____
O <sub>2</sub> Monitor	- continuous/hourly/daily/other _____
Colorimetric Tubes (type) _____	- continuous/hourly/daily/other _____
_____	_____
HNU/OVA	- continuous/hourly/daily/other _____
Other _____	- continuous/hourly/daily/other _____
_____	- continuous/hourly/daily/other _____

## Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

### 4. Emergency Procedures (should be modified as required for incident)

The following standard emergency procedures will be used by onsite personnel. The Site Safety Officer shall be notified of any onsite emergencies and be responsible for ensuring that the appropriate procedures are followed.

Personnel Injury in the Exclusion Zone: Upon notification of an injury in the Exclusion Zone, the designated emergency signal horn blast shall be sounded. All site personnel shall assemble at the decontamination line. The rescue team will enter the Exclusion Zone (if required) to remove the injured person to the hotline. The Site Safety Officer and Project Team Leader should evaluate the nature of the injury, and the affected person should be decontaminated to the extent possible prior to movement to the Support Zone. The onsite EMT shall initiate the appropriate first aid, and contact should be made for an ambulance and with the designated medical facility (if required). No persons shall reenter the Exclusion Zone until the cause of the injury or symptoms is determined.

Personnel Injury in the Support Zone: Upon notification of an injury in the Support Zone, the Project Team Leader and Site Safety Officer will assess the nature of the injury. If the cause of the injury or loss of the injured person does not affect the performance of site personnel, operations may continue, with the onsite EMT initiating the appropriate first aid and necessary follow-up as stated above. If the injury increases the risk to others, the designated emergency signal horn blast shall be sounded and all site personnel shall move to the decontamination line for further instructions. Activities on site will stop until the added risk is removed or minimized.

Fire/Explosion: Upon notification of a fire or explosion on site, the designated emergency signal horn blast shall be sounded and all site personnel assembled at the decontamination line. The fire department shall be alerted and all personnel moved to a safe distance from the involved area.

Personal Protective Equipment Failure: If any site worker experiences a failure or alteration of protective equipment that affects the protection factor, that person and his/her buddy shall immediately leave the Exclusion Zone. Reentry shall not be permitted until the equipment has been repaired or replaced.

Other Equipment Failure: If any other equipment on site fails to operate properly, the Project Team Leader and Site Safety Officer shall be notified and then determine the effect of this failure on continuing operations on site. If the failure affects the safety of personnel or prevents completion of the Work Plan tasks, all personnel shall leave the Exclusion Zone until the situation is evaluated and appropriate actions taken.

## Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

The following emergency escape routes are designated for use in those situations where egress from the Exclusion Zone cannot occur through the decontamination line: (describe alternate routes to leave area in emergencies)

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

In all situations, when an onsite emergency results in evacuation of the Exclusion Zone, personnel shall not reenter until:

1. The conditions resulting in the emergency have been corrected.
2. The hazards have been reassessed.
3. The Site Safety Plan has been reviewed.
4. Site personnel have been briefed on any changes in the Site Safety Plan.

### 5. Personal Monitoring

The following personal monitoring will be in effect on site:

Personal exposure sampling: none (describe any personal sampling programs being carried out on site personnel. This would include use of sampling pumps, air monitors, etc.)

\_\_\_\_\_

Medical monitoring: The expected air temperature will be 70°F. If it is determined that heat stress monitoring is required (mandatory if over 70°F), the following procedures shall be followed:

(describe procedures in effect, i.e., monitoring body temperature, body weight, pulse rate)

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

All site personnel have read the above plan and are familiar with its provisions.

	(name)	(signature)
Site Safety Officer	_____	_____
Project Team Leader	_____	_____
Other Site Personnel	_____	_____
	_____	_____
	_____	_____
	_____	_____
	_____	_____
	_____	_____

# Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

## Sample Hazardous Substance Information Form

COMMON NAME: #2 fuel oil

CHEMICAL NAME: \_\_\_\_\_

### I. PHYSICAL/CHEMICAL PROPERTIES

	Natural physical state: Gas _____ Liquid _____ Solid _____	SOURCE _____
(at ambient temps of 20°C-25°C)		
Molecular weight		
Density <sup>a</sup>	_____ g/g-mole	
Specific gravity <sup>a</sup>	_____ g/ml	
Solubility: water	_____ @ _____ °F/°C	
Solubility <sup>b</sup> :	_____ @ _____ °F/°C	
Boiling point	_____ @ _____ °F/°C	
Melting point	_____ @ _____ °F/°C	
Vapor pressure	_____ mmHg @ _____ °F/°C	
Vapor density	_____ @ _____ °F/°C	
Flash point	_____ @ _____ °F/°C	
(open cup _____; closed cup _____)		
Other: _____		

### II. HAZARDOUS CHARACTERISTICS

#### A. TOXICOLOGICAL HAZARD HAZARD?

	Yes	No
Inhalation	_____	_____
Ingestion	_____	_____
Skin/eye absorption	_____	_____
Skin/eye contact	_____	_____
Carcinogenic	_____	_____
Teratogenic	_____	_____
Mutagenic	_____	_____
Aquatic	_____	_____
Other: _____	_____	_____

CONCENTRATIONS  
(PEL, TLV, other)

SOURCE

#### B. TOXICOLOGICAL HAZARD HAZARD?

	Yes	No
Combustibility	_____	_____
Toxic byproduct(s):	_____	_____

CONCENTRATIONS

SOURCE

	Yes	No
Flammability	_____	_____

LFL

UFL

	Yes	No
Explosivity	_____	_____

LEL

UEL

<sup>a</sup>Only one is necessary.

<sup>b</sup>For organic compounds, recovery of spilled material by solvent extraction may require solubility data.



# Bensinger & Garrison Environmental, Inc. - SITE SAFETY PLAN

## C. REACTIVITY HAZARD

HAZARD?  
Yes No

CONCENTRATIONS

SOURCE

Reactivities:

## D. CORROSIVITY HAZARD

HAZARD?  
Yes No

CONCENTRATIONS

SOURCE

ph

Neutralizing agent:

## E. RADIOACTIVE HAZARD

HAZARD?  
Yes No

EXPOSURE RATE

SOURCE

Background

Alpha particles

Beta particles

Gamma radiation

## III. DESCRIPTION OF INCIDENT:

Quantity involved

Release information

Monitoring/sampling recommended

## IV. RECOMMENDED PROTECTION:

Worker

Public

## V. RECOMMENDED SITE CONTROL:

Hotline

Decontamination line

Command Post location

## VI. REFERENCES FOR SOURCES:

GATECO Oil Company

## MATERIAL SAFETY DATA SHEET

PAGE 1 OF 7

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)  
MSDS NO:

THE FOLLOWING INFORMATION IS FURNISHED SUBJECT TO THE DISCLAIMER ON THE BOTTOM OF THIS FORM

## SECTION 1 - PRODUCT IDENTIFICATION

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)

MANUFACTURER / DISTRIBUTOR:  
OIL COMPANY

## SYNONYMS:

NO. 2 FUEL OIL (0.05% SULFUR MAX);  
NO. 2 DIESEL FUEL W/0.05 SULFUR MAX; LOW  
SULFUR DIESEL FUEL (0.05%); NO. 2 FUEL OIL  
W/0.05 SULFUR MAXEMERGENCY PHONE NUMBERS:  
( )  
( )CHEMICAL FAMILY: PETROLEUM HYDROCARBON  
CHEMICAL FORMULA: MIXTURECAS NO: 64741-44-2  
PRODUCT CODE:

## SECTION 2 - PHYSICAL PROPERTIES

BOILING POINT  
350-660 FMELTING POINT  
N.A. FSPECIFIC GRAVITY(H2O=1)  
C.A. 0.8% SOLUBILITY IN WATER  
NEGLECTIBLEVAPOR DENSITY(AIR=1)  
4-5VAPOR PRESSURE  
1 - 10 MM HG @ 100FPH INFORMATION: PH: N.A. AT CONC.  
APPEARANCE: AMBER LIQUID

ODOR: FUEL OIL ODOR

## SECTION 3 - FIRE AND EXPLOSION HAZARD DATA

FLASH POINT 130 (MIN) F AUTOIGNITION TEMP C.A. 494 F EXPLOSIVE LIMITS (% BY VOLUME IN AIR)  
LOWER/UPPER: 0.7/ 5.0

NFPA CLASSIFICATION: HEALTH: 1 FIRE: 2 REACTIVITY: 1 OTHER:

## EXTINGUISHING MEDIA:

CLASS B FIRE EXTINGUISHING MEDIA SUCH AS HALON, CO2, OR DRY  
CHEMICAL CAN BE USED. FIRE FIGHTING SHOULD BE ATTEMPTED ONLY BY  
THOSE WHO ARE ADEQUATELY TRAINED.

## SPECIAL FIRE FIGHTING INSTRUCTIONS:

AVOID USE OF SOLID WATER STREAMS. AVOID EXCESSIVE WATER SPRAY  
APPLICATION. WATER CAN BE USED TO COOL EXPOSED SURFACES.

Att. Chip

GATECO Oil Company

## MATERIAL SAFETY DATA SHEET

PAGE 2 OF 7

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)  
 MSDS NO:

## SECTION 3 - FIRE AND EXPLOSION HAZARD DATA (CON'T)

STABILITY: THE MATERIAL IS STABLE AT 70 F, 760MM PRESSURE  
 CONDITIONS TO AVOID:  
 NO DATA AVAILABLE

HAZARDOUS DECOMPOSITION PRODUCTS:  
 CARBON MONOXIDE, ALDEHYDES, AROMATICS, OTHER  
 HYDROCARBONS

INCOMPATIBLE MATERIALS:  
 OXIDIZERS

HAZARDOUS POLYMERIZATION: WILL NOT OCCUR

## SECTION 4 - PRODUCT COMPOSITION AND EXPOSURE LIMITS

## EXPOSURE LIMITS FOR PRODUCT:

TLV

SOURCE

NO. 2 FUEL OIL (0.05% SULFUR M-  
 AX)

NONE ESTABLISHED

## COMPONENTS:

PERCENT RANGE

TLV

SOURCE

SATURATED HYDROCARBONS  
 (PARAFFINS & CYCLOPARAFFINS)  
 UNSATURATED HYDROCARBONS  
 (OLEFINS)  
 AROMATIC HYDROCARBONS  
 SULFUR  
 BENZENE

54.00- 85.00

0.00

( )

1.00- 6.00

0.00

( )

15.00- 45.00

0.00

( )

< .05  
 < .01

0.00

( )

10.00 PPM

(8 HR TWA) ACGIH

1.00 PPM

(8 HR TWA) OSHA

5.00 PPM

(STEL ) OSHA

\*\*\*  
 COMPLEX MIXTURE OF PARAFFINIC, CYCLOPARAFFINIC, OLEFINIC AND AROMATIC  
 HYDROCARBONS (PREDOMINANTLY C11 THROUGH C20).

GATECOIL Oil Company

## MATERIAL SAFETY DATA SHEET

PAGE 3 OF 7

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)  
MSDS NO:

## SECTION 5 - POTENTIAL HEALTH EFFECTS

## EYE:

SHORT-TERM LIQUID OR VAPOR CONTACT MAY RESULT IN SLIGHT EYE IRRITATION.

## SKIN:

PROLONGED OR REPEATED LIQUID CONTACT CAN CAUSE DEFATTING AND DRYING OF THE SKIN WHICH MAY PRODUCE SEVERE IRRITATION OR DERMATITIS.

## INHALATION:

HIGH VAPOR CONCENTRATIONS MAY PRODUCE HEADACHE, GIDDINESS, VERTIGO, AND ANESTHETIC STUPOR.

## INGESTION:

INGESTION MAY RESULT IN NAUSEA, VOMITING, DIARRHEA & RESTLESSNESS. ASPIRATION (BREATHING) OF VOMITUS INTO THE LUNGS MUST BE AVOIDED AS EVEN SMALL QUANTITIES IN THE LUNGS CAN PRODUCE CHEMICAL PNEUMONITIS AND PULMONARY EDEMA/HEMORRHAGE.

## ADDITIONAL TOXICITY INFORMATION:

THE INTERNATIONAL AGENCY FOR RESEARCH ON CANCER (IARC) HAS DETERMINED THAT THERE IS INADEQUATE EVIDENCE FOR THE CARCINOGENICITY OF FUEL OIL IN HUMANS.

LIFETIME SKIN PAINTING STUDIES IN ANIMALS WITH SIMILAR DISTILLATE FUELS HAVE PRODUCED WEAK CARCINOGENIC ACTIVITY FOLLOWING PROLONGED AND REPEATED EXPOSURE. REPEATED DERMAL APPLICATION HAS PRODUCED SEVERE IRRITATION AND SYSTEMIC TOXICITY IN SUBACUTE TOXICITY STUDIES. SOME COMPONENTS OF DISTILLATE FUELS, I.E., PARAFFINS AND OLEFINS, HAVE BEEN SHOWN TO PRODUCE A SPECIES SPECIFIC, SEX HORMONAL DEPENDENT KIDNEY LESION IN MALE RATS FROM REPEATED ORAL OR INHALATION EXPOSURE. SUBSEQUENT RESEARCH HAS SHOWN THAT THE KIDNEY DAMAGE DEVELOPS VIA THE FORMATION OF ALPHA-2U-GLOBULIN, A MECHANISM UNIQUE TO THE MALE RAT. HUMANS DO NOT FORM ALPHA-2U-GLOBULIN, THEREFORE, THE KIDNEY EFFECTS RESULTING FROM THIS MECHANISM ARE NOT RELEVANT IN HUMANS. NO. 2 FUEL OIL WAS FOUND TO BE POSITIVE IN A FEW MUTAGENICITY TESTS WHILE NEGATIVE IN THE MAJORITY OF OTHERS. THE EXACT RELATIONSHIP BETWEEN THESE RESULTS AND HUMAN HEALTH IS NOT KNOWN.

DIESEL ENGINE EXHAUST ANIMAL STUDIES - CHRONIC INHALATION STUDIES OF WHOLE DIESEL ENGINE EXHAUST IN MICE AND RATS PRODUCED A SIGNIFICANT INCREASE IN LUNG TUMORS. IARC HAS DETERMINED THAT THERE IS SUFFICIENT EVIDENCE FOR THE CARCINOGENICITY IN EXPERIMENTAL ANIMALS OF WHOLE ENGINE EXHAUST AND EXTRACTS OF DIESEL ENGINE EXHAUST PARTICLES. IARC DETERMINED THAT THERE IS ONLY LIMITED EVIDENCE FOR THE CARCINOGENICITY IN HUMANS OF DIESEL ENGINE EXHAUST. HOWEVER, IARC'S OVERALL EVALUATION HAS RESULTED IN THE IARC DESIGNATION OF DIESEL ENGINE EXHAUST AS PROBABLY CARCINOGENIC TO HUMANS (GROUP 2A) BECAUSE OF THE PRESENCE OF CERTAIN ENGINE EXHAUST COMPONENTS.

GATECO Oil Company

## MATERIAL SAFETY DATA SHEET

PAGE 4 OF 7

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)  
MSDS NO:

## SECTION 5 - POTENTIAL HEALTH EFFECTS (CON'T)

## EMERGENCY FIRST AID PROCEDURES

## EYE:

FLUSH EYES WITH LARGE AMOUNTS OF WATER FOR AT LEAST 15 MINUTES.  
IF SYMPTOMS OR IRRITATION OCCUR, CALL A PHYSICIAN.

## SKIN:

WASH WITH SOAP AND LARGE AMOUNTS OF WATER. REMOVE CONTAMINATED CLOTHING. IF SYMPTOMS OR IRRITATION OCCUR, CALL A PHYSICIAN.

## INHALATION:

MOVE PERSON TO FRESH AIR. IF NOT BREATHING, GIVE ARTIFICIAL RESPIRATION. CALL A PHYSICIAN.

## INGESTION:

DO NOT INDUCE VOMITING. DO NOT GIVE LIQUIDS. IMMEDIATELY CALL A PHYSICIAN.

## SECTION 6 - SPECIAL PROTECTION INFORMATION

## VENTILATION:

LOCAL OR GENERAL EXHAUST REQUIRED WHEN SPRAYING OR USING AT ELEVATED TEMPERATURES.

## RESPIRATORY PROTECTION:

APPROVED ORGANIC VAPOR CHEMICAL CARTRIDGE OR SUPPLIED AIR RESPIRATORS SHOULD BE WORN WHEN EXCESSIVE VAPORS OR MISTS ARE GENERATED. OBSERVE RESPIRATOR PROTECTION FACTOR CRITERIA CITED IN ANSI Z88.2 (1992). SELF-CONTAINED BREATHING APPARATUS SHOULD BE USED FOR FIRE FIGHTING.

## PROTECTIVE GLOVES:

NEOPRENE, NITRILE OR PVA GLOVES TO PREVENT SKIN CONTACT.

## OTHER PROTECTIVE EQUIPMENT:

USE MECHANICAL VENTILATION EQUIPMENT THAT IS EXPLOSION-PROOF.

GATECO Oil Company

## MATERIAL SAFETY DATA SHEET

PAGE 5 OF 7

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)  
MSDS NO:

## SECTION 7 - SPILL OR LEAK PROCEDURES

## ENVIRONMENTAL EFFECTS:

LIQUID CAN BE TOXIC TO AQUATIC LIFE.

## STEPS TO BE TAKEN IN CASE OF SPILL, LEAK OR RELEASE:

KEEP PUBLIC AWAY. SHUT OFF SOURCE OF LEAK IF POSSIBLE TO DO SO WITHOUT HAZARD. ELIMINATE ALL IGNITION SOURCES. ADVISE NATIONAL RESPONSE CENTER (800-424-8802) IF PRODUCT HAS ENTERED A WATER COURSE. ADVISE LOCAL AND STATE EMERGENCY SERVICES AGENCIES, IF APPROPRIATE. CONTAIN LIQUID WITH SAND OR SOIL. RECOVER AND RETURN FREE LIQUID TO SOURCE. USE SUITABLE SORBENTS TO CLEAN UP RESIDUAL LIQUIDS.

## WASTE DISPOSAL METHOD:

DISPOSE OF CLEANUP MATERIALS IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS.

## SECTION 8 - HANDLING AND STORAGE PRECAUTIONS

PRODUCT SHOULD BE HANDLED AND STORED IN ACCORDANCE WITH INDUSTRY ACCEPTED PRACTICES. COMPLY WITH ALL APPLICABLE OSHA, NFPA, AND CONSISTENT LOCAL REQUIREMENTS. USE APPROPRIATE GROUNDING AND BONDING PRACTICES. STORE IN PROPERLY CLOSED CONTAINERS THAT ARE APPROPRIATELY LABELED. DO NOT EXPOSE TO HEAT, OPEN FLAME, OXIDIZERS OR OTHER SOURCES OF IGNITION. AVOID SKIN CONTACT. EXERCISE GOOD PERSONAL HYGIENE INCLUDING REMOVAL OF SOILED CLOTHING AND PROMPT WASHING WITH SOAP AND WATER.

## SECTION 9 - HAZARD WARNING

## WARNING!

COMBUSTIBLE LIQUID  
HARMFUL OR FATAL IF SWALLOWED  
PRODUCES SKIN IRRITATION UPON PROLONGED OR REPEATED CONTACT

## SECTION 10 - COMMENTS

GATECO Oil Company

## MATERIAL SAFETY DATA SHEET

PAGE 6 OF 7

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)  
MSDS NO:

## SECTION 11 - REGULATORY INFORMATION

SARA TITLE III/SUPERFUND AMENDMENTS AND REAUTHORIZATION ACT OF 1986 -  
SECTIONS 302, 304, 311, 312 AND 313.

THE FOLLOWING REGULATIONS APPLY TO THIS PRODUCT:

SECTIONS 311 AND 312 - MATERIAL SAFETY DATA SHEET REQUIREMENTS:

40 CFR PART 370 (52 FR 38344 - OCTOBER 15, 1987).

DEPENDING ON LOCAL, STATE, AND FEDERAL REGULATIONS, MATERIAL SAFETY  
DATA SHEETS (MSDS'S) OR LISTS OF MSDS'S (PRODUCT NAMES) MAY BE  
REQUIRED TO BE SUBMITTED TO THE STATE EMERGENCY RESPONSE  
COMMISSION, LOCAL EMERGENCY PLANNING COMMITTEE, AND LOCAL FIRE  
DEPARTMENT IF YOU HAVE:10,000 POUNDS OR MORE OF AN OSHA HAZARDOUS SUBSTANCE OR  
500 POUNDS OR THE THRESHOLD PLANNING QUANTITY WHICHEVER  
IS LESS, OF AN EXTREMELY HAZARDOUS SUBSTANCE.\* REPORTABLE QUANTITY LEVELS CAN VARY FROM STATE TO STATE AND YEAR  
TO YEAR DEPENDING ON APPLICABLE STATE AND/OR FEDERAL REGULATIONS.THIS PRODUCT IS COVERED UNDER THE CRITERIA DEFINED IN OSHA'S HAZARD  
COMMUNICATION STANDARD 29 CFR 1910.1200 (52 FR 31852 - AUGUST 24,  
1987) AND SHOULD BE REPORTED UNDER THE FOLLOWING EPA HAZARD  
CATEGORIES:

XX IMMEDIATE (ACUTE) HEALTH HAZARD  
XX DELAYED (CHRONIC) HEALTH HAZARD  
XX FIRE HAZARD  
XX SUDDEN RELEASE OF PRESSURE HAZARD  
XX REACTIVE HAZARD

## DEPARTMENT OF TRANSPORTATION:

49 CFR 172.101 AS REVISED ON OCTOBER 1, 1993.

PROPER SHIPPING NAME:	FUEL OIL, NO. 2
DOT CLASSIFICATION:	3
DOT IDENTIFICATION NUMBER:	NA 1993
PACKING GROUP:	PG III

## SECTION 12 - REGULATIONS/COMMENTS CONTINUED

INFORMATION SUPPLIED BY:

PHONE: ( )

MSDS DATE: 09/20/93

DATE OF PREVIOUS MSDS: / /

GATECO Oil Company

## MATERIAL SAFETY DATA SHEET

PAGE 7 OF 7

PRODUCT NAME: NO. 2 FUEL OIL (0.05% SULFUR MAX)  
MSDS NO:

## \*\*\* DISCLAIMER \*\*\*

THIS INFORMATION RELATES ONLY TO THE SPECIFIC MATERIAL DESIGNATED AND MAY NOT BE VALID FOR SUCH MATERIAL USED IN COMBINATION WITH ANY OTHER MATERIALS OR IN ANY PROCESS. SUCH INFORMATION IS, TO THE BEST OF GATECO OIL COMPANY'S KNOWLEDGE AND BELIEF, ACCURATE AND RELIABLE AS OF THE DATE INDICATED. HOWEVER, NO REPRESENTATION, WARRANTY OR GUARANTEE IS MADE AS TO ITS ACCURACY, RELIABILITY OR COMPLETENESS. IT IS THE USER'S RESPONSIBILITY TO SATISFY HIMSELF AS TO THE SUITABLENESS AND COMPLETENESS OF SUCH INFORMATION FOR HIS OWN PARTICULAR USE.